Bid Addendum Report

Jagadish Kairatiya ko Ghar dekhi School samma road P.C.C..

Janaki Rural Municipality, Banke

Janaki Rural Municipality, Banke khajura,khurd Nepalgunj, Banke Nepal

Addendum No: 1

Published On: 05-06-2018 00:00

Invitation No: 18/JANAKI/NCB/Road/074/075

Dated On: 23-05-2018 00:00

Chapter: Evaluation and Qualification Criteria

Sl. No.	Criteria Title	
1	Up to date Firm/Company Registration Certificate	
2	VAT and PAN Registration Certificates	
3	Tax Clearance Certificate/tax returns evidance Power of Attorney	
4	A written declaration made by the Bidder stating that the Bidder is not ineligible to participate in the bid; has no conflict of interest in the bid procurement proceedings and has not been punished for the profession or business related offence.	
5	Other documents as needed	

Chapter: Bill of Quantities

1 Provisional Sum Procument Item Details							
1	Notice board.	nos	1.0				
2 C	onstruction work						
	Proc	ument Item Details					
SL.	Item Description	Unit	Quantity	Bidder's Rate	Total Amount		
1	Excavation for foundation through all types of soil including relevant lift and disposal for depth upto 1.5 m.	m3	10.7				
2	Dry Stone soling in the base of foundation of drain with proper watering and compaction	m3	7.64				
3	Providing and placing manually mixed cement concrete [cement (1); sand (3); aggregate (6)]	m3	42.04				
4	Providing and laying 1:4 brick masonry in manual	m3	23.92				
5	Local wood formwork in the drain	m2	161.0				
6	Providing and applying 12.5mm thick 1:4 cement plaster including mortar mixing, placing & curing etc. complete as per specification lead 30 m (manual mixing)	m2	300.0				
7	Site Clearance Clearing of grass, removing roots breaking sods, levelling the surface and disposal 10 m.	m2	675.0				
8	Roadway filling and embankment work.	m3	339.5				
9	Providing and laying of flat brick soling work as sub- base work for providing uniform base the plain cement concrete work	m3	63.47				
10	Providing, laying, plain cement concrete (PCC.) work 1:2:4 as the pavement work.	m3	63.47				