



जानकी गाउँपालिका गाउँ कार्यपालिकाको कार्यालय

जानकी गाउँपालिका
गाउँ कार्यपालिकाको कार्यालय
मानपुर, बाँके
लुम्बिनी प्रदेश, नेपाल
२०७३

मानपुर, बाँके
लुम्बिनी प्रदेश

मिति : २०८२/०७/२०

प.सं. : ०८२/८३

च.नं. : ३८६

दररेट पेश गर्ने सम्बन्धी सूचना

सूचना प्रकाशित मिति : २०८२/०७/२०

१. जानकी गाउँपालिकाको आ.व. २०८२/८३ को पालिका स्तरीय स्वीकृत कार्यक्रम अनुसार तपसिल बमोजिमको निर्माण कार्य सोझै खरिद विधिबाट गर्नुपर्ने भएकाले इच्छुक निर्माण सेवा फर्मले यो सूचना प्रकाशित भएको मितिले ७ दिन भित्र दररेट यस गाउँपालिकामा पेश गर्न हुन यो सूचना प्रकाशित गरिएको छ ।

२.

क्र.स.	विवरण	लागत अनुमान रकम (मु.अ. कर बाहेक)	दररेट पेश गर्ने अन्तिम समय	कैफियत
१	इन्द्रपुर स्वास्थ्य चौकीको माथिलो तल्लामा १ कोठे भवन निर्माण	रु. ४,३०,५५६/९६	मिति: २०८२/०७/२६ (कार्यालय समय भित्र)	

३. दररेट पेश गर्ने फर्मले अनिवार्य रूपमा दररेट पेश गर्ने व्यहोरा सम्बन्धको लिखित निवेदन सहित नवीकरण भएको फर्म/कम्पनी दर्ताको प्रमाणपत्रको प्रतिलिपि, मु.अ. कर दर्ताको प्रमाणपत्रको प्रतिलिपि र आ.व. २०८१/८२ को करचुक्ताको प्रमाणपत्रको प्रतिलिपि संलग्न गरि पेश गर्नु पर्नेछ ।

४. उक्त कार्यका लागि आवश्यक BOQ यस कार्यालयको वेबसाईट www.janakimun.banke.gov.np बाट डाउनलोड गर्न सकिने छ ।

५. BOQ मा आफुले कबोल गरेको रकम अंक र अक्षरमा स्पष्ट बुझिने गरि लेखेर पेश गर्नुपर्ने छ । अंक र अक्षरमा फरक पर्न गएमा अक्षरलाई मान्यता दिइनेछ । केरमेट भएको BOQ लाई मुल्यांकनमा समावेश गरिने छैन ।

६. जानकी गाउँपालिकामा आ.व. २०८२/८३ को लागि सूचिकृत नभएका फर्महरूको दररेट मान्य हुने छैन ।

प्रजेश कुमार आले
इन्जिनियर

परशुराम उपाध्याय
प्रमुख प्रशासकीय अधिकृत

परशुराम उपाध्याय
प्रमुख प्रशासकीय अधिकृत

"व्यावसायिक र सिर्जनशील प्रशासन विकास : समृद्धि र सुशासन"

website: www.janakimunbanke.gov.np, email-id: info@janakimunbanke.gov.np, janakirm.banke@gmail.com

Janaki Rural Municipality
Office of the Rural Executive
Manpur, Banke



Bill OF Quantities

स्वीकृत
प्रमाणित
२८३५/१
२०८१/६/२०

परशुराम उपाध्याय
प्रमुख प्रशासकीय अधिकृत

Project Name :- इन्द्रपुर स्वास्थ्य चौकीको माथिलो तल्लामा १ कोठे भवन निर्माण

Project Location :- Janaki gaupalika ward no. 3 banke

पालिका स्तरिय योजना

FY: 2082/83

Janaki Rural Municipality
Office of the Rural Executive
Manpur, Banke
Lumbini, province
Bill of Quantities

Project Name :- इन्द्रपुर स्वास्थ्य चौकीको माथिलो तल्लामा १ कोठे भवन निर्माण
Project Location :- Janaki gaupalika ward no. 3 banke



SN	Description of Items	Quantity	Unit	Figures	Contractor's Rate in NRs.		Amounts in NRs.	Remarks
					Rate in words			
A	General Work							
1	Providing and fixing of information sign board of standard size 1.2X0.9 Mtr. Including painting, wording and erection all complete.	1.00	Ls	1,000.00	one Thousand rupees only.			
B	Civil Work							
1	RCC with Plain cement concrete work of grade M15 Ratio including material and labour required for mixing, placing in position, vibrating, compacting, finishing, curing and all other incidentals required to produce concrete of specified strength.	0.49	Cum					
2	Form work	3.25	Sqm					
3	Reinforcement Work	47.27	Ks					
4	First Class Chimney Made brick masonry work in 1:4 cement mortar including full materials and other incidentals required to complete the work.	7.21	Cum					
5	12.5mm thick cement sand plaster in (1:4) ratio on wall of good finish including racking the joint, wetting of surfaces & curing the work all complete.	75.06	Sqm					
6	Colouring in interior and exterior side two coat of Plastic Emulsion paint with one coat primer of approved color over properly cleaned surface after rendering the surface all complete as per requirement and instruction	75.06	Sqm					
7	Supply and Fabrication of Medium Class MS Circular / Square Pipe	231.51	Kg					
8	CGI Sheet work 38mm thick colour cgi sheet fitting And fixing all as complete.	17.10	Sqm					
9	Plain cgi sheet as for rigid roof	8.00	Rm					
10	(Fix partition) Supplying and Fixing of aluminium fix partition section size 101*45*1.3 mm thickness aluminium frame with 5 mm clear glass or 9mm Nepal board with all Necessary fittings and all complete.	4.95	Sqm					

परमेश्वर प्रशासकीय अधिकारी
परमेश्वर प्रशासकीय अधिकारी

प्रवेश कुमार शर्मा
इन्जिनियर

सह-इन्जिनियर
सह-इन्जिनियर

11	MF Suspended Ceiling with MPL Board (for CGI Roofing Ceiling Supply fixing, fitting inposting GI under Frame using Gypsteel branded chanel and fixing 9-12.50mm thick MPL Board Ceiling in position GI underframe using Gypsteel branded (Metalized polyester laminated) chanel fixing joints with compounds all complete for designed ceiling.	24.50	Sqm				
12	Electrict Work like power point, plug, light bulb, 2 ceiling fan etc all complot as per site engineer.	1.00	Job				
13	Irin Grill work in window fitting and fixing as all complete.	89.60	Kg				
14	38mm thick cement concrete work of grade M15 Ratio including material and labour required for mixing, placing in position, finishing, curing and all other incidentals required to produce concrete of specified strength.	24.50	Sqm				
15	Local Comode complete set with S Trap	1.00	Nos				
16	(50x40)cm Porcelain clay white glaze Wash basin regular complete set.	1.00	Nos				
17	Plumbing Works	1.00	Job				
18	Dismantling of existing structures like brick masomary walls	1.00	Job				
Sub Total							
VAT@13%							
Grand Total NRS							

In Words Rs. :-

Name of Firm :-

Address :-

Firm seal :-

Name of the representative :-

Signature :-

Date :-



प्रमुख प्रशासकीय अधिकारी
परचुराज उपप्रभाग

प्रजेश कुमार आले
इन्जिनियर

20/03/2023

20/03/2023

20/03/2023